DEPARTMENT OF INDUSTRIES AND COMMERCE, BANGALORE.

Notification No. 98, *dated* 12*th July* 1935.

1. Notice is hereby given that sealed tenders will be received at the Office of the Superintendent, Government Industrial and Testing Laboratory, Malleswaram, Bangalore up to 31st July 1935, (3 P.M.) for Constructing a Zinc Shed in the Compound of the Sandal Koti. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within three weeks of the date of intimation of acceptance of the tender.

2. Each tender must be accompanied by a deposit of Rupees Two Hundred only in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a Zinc Shed in the Premises of the Government Industrial and Testing Laboratory, Bangalore" in default of which, the tender will be rejected.

3. The final acceptance of any tender will rest with the Director of Industries and Commerce in Mysore, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for rejection of any tender.

4. Within three days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

5. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

6. Rates once tendered will not be enhanced on any account.

7. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Industries and Commerce in Mysore, Bangalore will be final and legally binding.

8. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities for constructing Zinc Shed in the Premises of the Government Industrial and Testing Laboratory, Bangalore.

No.	Items of work	Quantity
1	Earthwork excavation	954·87 C.ft.
2	Burnt size stone in clay foundation quantity as per earthwork	711·74 ,,
3	(*a*) Brick in clay wall	1095·6 ,,
	(*b*) Brick in chunam for pillars	185·00 ,,
4	Pillars in burnt brick in chunam	108·0 ,,
5	Burnt stone slabs one line dressed for pillars	72·0 S.ft.
6	Chunam plastering the walls	2379·75 ,,
7	Chunam plastering the pillars	109·5 C.ft.
8	Mild Steel Trusses for 20′ span including hoisting and fixing	....
9	Corrugated zinc sheet roofing including fixing	9·16 Sqr.
10	Angle Iron perlins including fixing charges	168 R.ft.
11	Ridge zinc sheet piece 2′ broad including fixing	....
12	Flooring with burnt stone slab one line dressed 5″ thick over 3″ line concrete and cement pointing	500 S.ft.
13	Stone pillars 4″ T. 1′ broad	28·5 R.ft.
14	$3\frac{1}{2}''\times3\frac{1}{2}''$ groove cutting charges	....
15	Girder for the above $3''\times1\frac{1}{2}''$	16 R.ft.
16	Teakwood rafters including fixing charges	1·250C.ft.
17	Angle Iron $2''\times\frac{1}{4}''$	32 R.ft.
18	Size stone on top of the pillars $1\frac{1}{2}'\times1\frac{1}{2}'$	$13\frac{1}{2}$ S.ft.
19	Girders $6''\times4\frac{1}{2}''-2\times15'$	30 R.ft.
20	Girders Cross—$6\times7'$	42 ,,

Further details can be had in the Office of the undersigned on any working day from 9 A.M. to 11 A.M.

K. A. N. RAO,
Superintendent.